

LEGEND:



- INDICATES EXISTING CONTOURS SHOWN AT 0.1m INTERVALS
- INDICATES PROPOSED CONTOURS SHOWN AT 0.1m INTERVALS
- INDICATES EXTENT OF PROPOSED EARTHWORK

NOTES:

- EXISTING CONTOURS ARE FROM 'ENVIVO' SITE SURVEY UNDERTAKEN IN FEB 2021.
- PROPOSED CONTOURS SHOWN ARE FINISHED GROUND LEVELS.

RESOURCE CONSENT

**GRANTED
29/06/2021**

HUTT CITY COUNCIL



This design and drawing shall only be used for the purpose for which it was supplied and shall not be altered or reproduced without the permission of Envelope Engineering Limited. No liability shall be accepted for unauthorised use of this design and drawing.

REV	NOTES	BY	DATE
RC1	ISSUED FOR RESOURCE CONSENT	AH	24/01/2021

PROJECT:
WILLIAMS CORPORATION LTD
4 JOHNSTON GROVE, TAITA
LOWER HUTT

TITLE:

PROPOSED CONTOURS PLAN



LEVEL 1, 68 DIXON STREET, TE ARO, WELLINGTON 6011
W W . E N V E L O P E . E N G . C O . N Z

DESIGNED: AH	DRAWN: AH
CHECKED: RR	DATE: 29/03/2021
SCALE A1: 1:125	SCALE A3: 1:250
STATUS: RESOURCE CONSENT	
PROJECT No: 1606-01	DRAWING No: 210
	REVISION: RC1

LEGEND:

- INDICATES CUT CONTOURS (MAX HEIGHT = -0.25m, VOLUME = -0m³) SHOWN AT 0.1m INTERVALS
- INDICATES FILL CONTOURS (MAX HEIGHT = 0.95m, VOLUME = +486m³) SHOWN AT 0.1m INTERVALS
- INDICATES EXTENT OF PROPOSED EARTHWORK AREA = 1780m²

NOTES:

- EXISTING CONTOURS ARE FROM 'ENVIVO' SITE SURVEY UNDERTAKEN IN FEB 2021.
- CUT/FILL CONTOURS SHOWN ARE THE DIFFERENCE BETWEEN EXISTING GROUND LEVEL AND FINISHED GROUND LEVELS.
- INDICATIVE VOLUMES

3.1. TOPSOIL STRIP	120	m³
3.2. TOPSOIL RESPREAD	95	m³
3.3. BULK CUT	0	m³
3.4. BULK FILL	286	m³
3.5. PAVEMENTS	50	m³
3.6. BUILDING PLATFORMS	235	m³

RESOURCE CONSENT

GRANTED
29/06/2021

HUTT CITY COUNCIL



JOHNSTON GROVE

